



STRUCTALL BUILDING SYSTEMS

EPS/OSB FOAM CORE ROOF PANELS - METAL SKIN



1 CLEAR SPAN ISOMETRIC
N.T.S.



2 PANEL INTERLOCK DETAIL
N.T.S.

GENERAL NOTES (OSB & SHINGLES):

- THIS DESIGN COMPLIES WITH THE STRUCTURAL PROVISIONS OF THE 2009 & 2012 INTERNATIONAL BUILDING CODE AND THE 2009 & 2012 INTERNATIONAL RESIDENTIAL CODE.
- THIS SHEET CERTIFIES STRUCTURAL DESIGN ONLY (WATERPROOFING BY OTHERS). TOTAL SUPERIMPOSED DEAD LOAD ON ANY PANEL SHALL NOT EXCEED 5 PSF, AND THIS WEIGHT SHALL BE SUBTRACTED FROM THE LIVE LOAD ALLOWABLE VALUES IN THE PANEL ROOF SPAN CHARTS WHEN USING THIS INSTALLATION METHOD.
- EXAMPLE: IN A 30PSF WIND PRESSURE/SNOW LOAD ZONE, WITH THE ADDITION OF THE MAXIMUM ALLOWABLE PSF DEAD LOAD, THE MODIFIED MAXIMUM ALLOWABLE PANEL SPAN SHALL BE GOVERNED BY LOADING CRITERIA OF 35PSF.
- SEAL ALL SEAMS AND CONNECTIONS WITH STRUCTURAL GRADE ADHESIVE SEALANT (1500 PSI MIN. TENSILE LOAD STRENGTH), AND CLEAN ROOF OF ANY DIRT, GREASE, WATER OR OIL.
- ALL FASTENERS TO BE #8 OR GREATER SAE GRADE 5, UNLESS NOTED OTHERWISE. FASTENERS SHALL BE CADMIUM-PLATED OR OTHERWISE CORROSION-RESISTANT MATERIAL AND SHALL COMPLY WITH "SPECIFICATIONS FOR ALUMINUM STRUCTURES" SECTION 5.2.1 BY THE ALUMINUM ASSOCIATION, INC., & ANY APPLICABLE FEDERAL, STATE, AND/OR LOCAL CODES.
- THE CONTRACTOR SHALL CAREFULLY CONSIDER POSSIBLE IMPOSING LOADS ON ROOF, INCLUDING BUT NOT LIMITED TO ANY CONCENTRATED LOADS WHICH MAY JUSTIFY GREATER DESIGN CRITERIA. THIS ADDITIONAL ROOF LOAD CRITERIA SHALL BE PROPERLY ANALYZED BY A LICENSED ENGINEER OR REGISTERED ARCHITECT.
- THE CONTRACTOR IS RESPONSIBLE TO INSULATE ALL MEMBERS FROM DISSIMILAR MATERIALS TO PREVENT ELECTROLYSIS. PANELS TO BE BY STRUCTALL BUILDING SYSTEMS ONLY, EXCEPT AS EXPRESSLY PROVIDED HEREIN. NO CERTIFICATIONS OR AFFIRMATIONS ARE INTENDED.
- THIS DETAIL ONLY VALID WHEN SIGNED AND SEALED BY FRANK L. BENNARDO, P.E.
- ENGINEER SEAL AFFIXED HERE TO VALIDATES STRUCTURAL DESIGN AS SHOWN ONLY. USE OF THIS SPECIFICATION BY CONTRACTOR, ET AL, INDENIIFIES & SAVES HARMLESS THIS ENGINEER FOR ALL COST & DAMAGES INCLUDING LEGAL FEES & APPELLATE FEES RESULTING FROM MATERIAL FABRICATION, SYSTEM ERECTION, & CONSTRUCTION PRACTICES BEYOND THAT WHICH IS CALLED FOR BY LOCAL, STATE, & FEDERAL CODES & FROM DEVIATIONS OF THIS PLAN.
- THE SYSTEM DETAILED HEREIN IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SPECIFIC SITE. FOR SITE CONDITIONS DIFFERENT FROM THE CONDITIONS DETAILED HEREIN, A LICENSED ENGINEER OR REGISTERED ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE IN CONJUNCTION WITH THIS DOCUMENT.
- ** ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

MAXIMUM ALLOWABLE DESIGN PRESSURES:

AS NOTED IN CLEAR SPAN TABLE

DESIGN NOTES:

POSITIVE AND NEGATIVE DESIGN PRESSURES CALCULATED FOR USE WITH THIS SYSTEM SHALL BE DETERMINED BY OTHERS ON A JOB-SPECIFIC BASIS IN ACCORDANCE WITH THE GOVERNING CODE. SITE-SPECIFIC LOAD REQUIREMENTS FOR LIVE LOAD, WIND LOAD, SNOW LOAD OR ANY LOAD COMBINATION SHALL BE DETERMINED IN ACCORDANCE WITH ASCE 7 AND THE 2009 & 2012 INTERNATIONAL BUILDING CODE (AS APPLICABLE) BY SEPARATE ENGINEERING CERTIFICATION AND SHALL BE LESS THAN OR EQUAL TO THE POSITIVE OR NEGATIVE DESIGN PRESSURE CAPACITY VALUES LISTED HEREIN FOR ANY ASSEMBLY AS SHOWN.

GENERAL NOTES:

- THIS SPECIFICATION HAS BEEN DESIGNED AND SHALL BE FABRICATED IN ACCORDANCE WITH THE REQUIREMENTS OF THE 2009 & 2012 INTERNATIONAL BUILDING CODES, THE 2009 & 2012 INTERNATIONAL RESIDENTIAL CODE, CONTRACTOR SHALL INVESTIGATE AND CONFORM TO ALL LOCAL BUILDING CODE AMENDMENTS WHICH MAY APPLY. DESIGN CRITERIA BEYOND AS STATED HEREIN MAY REQUIRE ADDITIONAL SITE-SPECIFIC SEALED ENGINEERING.
- SEISMIC DESIGN HAS NOT BEEN CONSIDERED.
- COMPOSITE ROOF PANELS SHALL COMPLY WITH CHAPTER 7 SECTION 719 (IBC 2009) CHAPTER 720 (2012 IBC), CHAPTER 8 SECTION 803, CLASS A INTERIOR FINISH, AND CHAPTER 26 SECTION 2603 OF THE 2009 & 2012 IBC.
- NO $33-1/3\%$ INCREASE IN ALLOWABLE STRESS HAS BEEN USED IN THE DESIGN OF THIS SYSTEM.
- DESIGN PRESSURES AS NOTED HEREIN ARE BASED ON A MAXIMUM TESTED PRESSURE DIVIDED BY A 2.0 FACTOR OF SAFETY.
- THE ARCHITECT/ENGINEER OF RECORD FOR THE PROJECT SHALL BE RESPONSIBLE FOR THE INTEGRITY OF ALL SUPPORTING SURFACES TO THIS DESIGN WHICH SHALL BE COORDINATED BY THE PERMITTING CONTRACTOR.
- SEPARATE "SITE-SPECIFIC SEALED ENGINEERING" SHALL BE REQUIRED IN ORDER TO DEVIATE FROM LOADS, DEFLECTIONS, OR SPANS CONTAINED HEREIN. LINEAR INTERPOLATION OF THE ALLOWABLE SPAN TABLES LISTED HEREIN SHALL NOT BE PERMITTED. CONTACT THIS ENGINEER FOR ALTERNATE SPAN CALCULATIONS AS MAY BE REQUIRED.
- THE SYSTEM DETAILED HEREIN IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SPECIFIC SITE. FOR SITE CONDITIONS DIFFERENT FROM THE CONDITIONS DETAILED HEREIN, A LICENSED ENGINEER OR REGISTERED ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS FOR USE IN CONJUNCTION WITH THIS DOCUMENT.
- THE CONTRACTOR SHALL CAREFULLY CONSIDER POSSIBLE IMPOSING LOADS ON ROOF, INCLUDING BUT NOT LIMITED TO ANY CONCENTRATED LOADS WHICH MAY JUSTIFY GREATER DESIGN CRITERIA. THIS ADDITIONAL ROOF LOAD CRITERIA SHALL BE PROPERLY ANALYZED BY A LICENSED ENGINEER OR REGISTERED ARCHITECT.
- ENGINEER SEAL AFFIXED HERE TO VALIDATES STRUCTURAL DESIGN AS SHOWN ONLY. USE OF THIS SPECIFICATION BY CONTRACTOR, ET AL, INDENIIFIES & SAVES HARMLESS THIS ENGINEER FOR ALL COST & DAMAGES INCLUDING LEGAL FEES & APPELLATE FEES RESULTING FROM MATERIAL FABRICATION, SYSTEM ERECTION, & CONSTRUCTION PRACTICES BEYOND THAT WHICH IS CALLED FOR BY LOCAL, STATE, & FEDERAL CODES & FROM DEVIATIONS OF THIS PLAN.
- EXCEPT AS EXPRESSLY PROVIDED HEREIN, NO ADDITIONAL CERTIFICATIONS OR AFFIRMATIONS ARE INTENDED.
- ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE THIS CERTIFICATION.

TABLE VALUE DERIVATIONS:

- PANEL PROPERTIES:
- PANEL STRUCTURAL PROPERTIES DERIVED FROM CERTIFIED TEST REPORTS NOS. TT-506027B, 506027C, 506027D, 509014A, 509014B BY TERRAPIN TESTING, ESP012351P-1, ESP012351P-2, ESP012351P-3, ESP012351P-3A, ESP012351P-4, ESP012351P-5, ESP012351P-6, EXP012351P-6A, ESP012351P-7, ESP012351P-8, ESP012351P-9, ESP012351P-9A BY ELEMENT MATERIALS TECHNOLOGY.
 - PANEL DEAD LOADS HAVE BEEN FACTORED INTO CALCULATIONS FOR LIVE LOADS OR UPLIFT AS WELL AS CALCULATIONS FOR PANEL PROPERTIES.

FRANK L. BENNARDO, P.E.
 STATE SEAL
 INDICATED BELOW
 08/07/2014
 VALID FOR (1) JOB(S) ONLY
 VALID ONLY WITH RAISED ENGINEER SEAL

POWERED BY THE INNOVATIONS OF
ENGINEERING EXPRESS
 EXPERIENCE MORE AT WWW.ENGEXP.COM

FRANK L. BENNARDO, P.E.
 160 SW 12th AVENUE, #106
 DEERFIELD BEACH, FL 33442
 PH: (954) 354-0660 Fax: (954) 354-0443

STRUCTALL BUILDING SYSTEMS
 350 BURBANK ROAD
 OLDSMAR, FL 34677
 PH: (813) 855-2627

LA: 30341
 GA: 27555
 FL: 27525
 IN: 1060688
 ME: 10478
 MD: 28152
 MA: 43224
 NH: 43001
 MI: 16927
 MO: 2003019621
 HI: 19491
 NC: 10624
 NJ: 248604353500
 OH: 9602224
 OR: 66438
 PA: 96060991
 RI: 7928
 SC: 21507
 TX: 96064
 VT: 8182
 WA: 0402 038109
 DC: 15009, CA 2282
 ID: 110930, CA 2030

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	RWN	TSB	08/05/14

SCALE: 14-1745
 PAGE DESCRIPTION: 1

THIS DOCUMENT IS THE PROPERTY OF FRANK L. BENNARDO, P.E. AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN CONSENT OF FRANK L. BENNARDO, P.E. ALL ALTERATIONS, ADDITIONS, OR OTHER MARKINGS TO THIS DOCUMENT ARE NOT PERMITTED AND INVALIDATE OUR CERTIFICATION.

MAXIMUM ALLOWABLE CLEAR SPAN TABLE:

Live Load &/or Uplift w/ 5/8" Max OSB	Deflection Limit (L/...)	3" Panels		4" Panels		6" Panels			
		Alum Skin	1-LB EPS	Alum Skin	1-LB EPS	Alum Skin	1-LB EPS	Alum Skin	1-LB EPS
+/- 13 psf	120	0.024"	12-12"	0.024"	15-4"	0.024"	18-1"	0.030"	20-2"
+/- 13 psf	180	0.030"	16-0"	0.030"	17-3"	0.030"	18-1"	0.030"	20-5"
+/- 13 psf	240	0.030"	13-1"	0.030"	13-5"	0.030"	16-2"	0.030"	18-8"
+/- 18 psf	120	0.030"	10-4"	0.030"	12-2"	0.030"	14-8"	0.030"	18-1"
+/- 18 psf	180	0.030"	11-9"	0.030"	13-11"	0.030"	15-3"	0.030"	17-8"
+/- 18 psf	240	0.030"	10-4"	0.030"	12-2"	0.030"	14-4"	0.030"	17-6"
+/- 23 psf	120	0.030"	9-4"	0.030"	11-1"	0.030"	13-4"	0.030"	16-6"
+/- 23 psf	180	0.030"	10-11"	0.030"	12-5"	0.030"	14-0"	0.030"	15-10"
+/- 23 psf	240	0.030"	9-7"	0.030"	12-5"	0.030"	12-10"	0.030"	15-10"
+/- 28 psf	120	0.030"	8-8"	0.030"	11-7"	0.030"	12-9"	0.030"	15-3"
+/- 28 psf	180	0.030"	11-4"	0.030"	11-8"	0.030"	14-3"	0.030"	14-5"
+/- 28 psf	240	0.030"	10-0"	0.030"	12-6"	0.030"	11-8"	0.030"	14-5"
+/- 33 psf	120	0.030"	9-3"	0.030"	10-9"	0.030"	11-10"	0.030"	13-4"
+/- 33 psf	180	0.030"	8-7"	0.030"	10-6"	0.030"	11-10"	0.030"	13-4"
+/- 33 psf	240	0.030"	7-9"	0.030"	10-4"	0.030"	11-5"	0.030"	13-4"
+/- 43 psf	120	0.030"	8-10"	0.030"	9-2"	0.030"	10-10"	0.030"	12-9"
+/- 43 psf	180	0.030"	9-11"	0.030"	10-3"	0.030"	11-3"	0.030"	12-8"
+/- 43 psf	240	0.030"	8-3"	0.030"	9-11"	0.030"	11-3"	0.030"	12-8"
+/- 48 psf	120	0.030"	7-6"	0.030"	8-10"	0.030"	10-12"	0.030"	12-8"
+/- 48 psf	180	0.030"	8-2"	0.030"	9-6"	0.030"	10-5"	0.030"	11-9"
+/- 48 psf	240	0.030"	7-10"	0.030"	9-3"	0.030"	10-5"	0.030"	11-9"
+/- 53 psf	120	0.030"	8-2"	0.030"	8-5"	0.030"	9-6"	0.030"	11-9"
+/- 53 psf	180	0.030"	8-2"	0.030"	8-5"	0.030"	9-11"	0.030"	11-2"
+/- 53 psf	240	0.030"	8-2"	0.030"	8-2"	0.030"	9-11"	0.030"	11-2"
+/- 58 psf	120	0.030"	8-7"	0.030"	8-7"	0.030"	9-5"	0.030"	10-8"
+/- 58 psf	180	0.030"	8-7"	0.030"	8-7"	0.030"	9-5"	0.030"	10-8"
+/- 58 psf	240	0.030"	8-7"	0.030"	8-7"	0.030"	9-5"	0.030"	10-8"
+/- 63 psf	120	0.030"	7-11"	0.030"	8-3"	0.030"	9-0"	0.030"	10-2"
+/- 63 psf	180	0.030"	8-3"	0.030"	8-10"	0.030"	8-3"	0.030"	10-2"
+/- 63 psf	240	0.030"	8-3"	0.030"	8-8"	0.030"	9-0"	0.030"	10-2"
+/- 68 psf	120	0.030"	7-10"	0.030"	7-10"	0.030"	8-8"	0.030"	9-10"
+/- 68 psf	180	0.030"	7-10"	0.030"	7-10"	0.030"	8-8"	0.030"	9-10"
+/- 68 psf	240	0.030"	7-10"	0.030"	7-10"	0.030"	8-8"	0.030"	9-10"
+/- 76 psf	120	0.030"	7-6"	0.030"	7-6"	0.030"	8-8"	0.030"	9-10"
+/- 76 psf	180	0.030"	7-3"	0.030"	7-3"	0.030"	8-4"	0.030"	9-5"
+/- 76 psf	240	0.030"	7-3"	0.030"	7-3"	0.030"	8-4"	0.030"	9-5"
+/- 78 psf	120	0.030"	7-3"	0.030"	7-3"	0.030"	8-4"	0.030"	9-5"
+/- 78 psf	180	0.030"	7-3"	0.030"	7-3"	0.030"	8-9"	0.030"	8-10"
+/- 78 psf	240	0.030"	7-3"	0.030"	7-3"	0.030"	8-9"	0.030"	8-10"
+/- 83 psf	120	0.030"	7-3"	0.030"	7-3"	0.030"	8-6"	0.030"	8-7"
+/- 83 psf	180	0.030"	8-6"	0.030"	8-6"	0.030"	8-7"	0.030"	8-7"
+/- 83 psf	240	0.030"	8-6"	0.030"	8-6"	0.030"	8-7"	0.030"	8-7"
+/- 88 psf	120	0.030"	8-3"	0.030"	8-3"	0.030"	8-3"	0.030"	8-4"
+/- 88 psf	180	0.030"	8-3"	0.030"	8-3"	0.030"	8-3"	0.030"	8-4"
+/- 88 psf	240	0.030"	8-3"	0.030"	8-3"	0.030"	8-3"	0.030"	8-4"
+/- 93 psf	120	0.030"	8-0"	0.030"	8-0"	0.030"	8-0"	0.030"	8-1"
+/- 93 psf	180	0.030"	8-0"	0.030"	8-0"	0.030"	8-0"	0.030"	8-1"
+/- 93 psf	240	0.030"	8-0"	0.030"	8-0"	0.030"	8-0"	0.030"	8-1"

*OSB SELF WEIGHT NOT TO EXCEED 2.08 PSF

- OTHER CONSIDERATIONS:**
- FRONT OVERHANG MAY BE UP TO 3'-0" WITH VALUES LISTED HEREIN. MAXIMUM UNSUPPORTED SIDE OVERHANG IS 25% OF LAST PANEL WIDTH (i.e. 12" MAX FOR 48" PANEL WIDTH).
 - ROOF PITCH NOT TO EXCEED 3:12


DRAFT

CLEAR SPAN TABLE USE INSTRUCTIONS:

- DETERMINE TYPE OF ENCLOSURE TO BE COVERED (OPEN, SCREENED WALLS, OR FULLY ENCLOSED).
- VERIFY APPROPRIATE DESIGN LOAD WITH GOVERNING MUNICIPALITY AND BUILDING CODES IN EFFECT FOR THE PROJECT LOCATION AND USING 2009 OR 2012 INTERNATIONAL BUILDING CODE (AS APPLICABLE) AS PROVIDED BY REGISTERED ARCHITECT. SEPARATE ENGINEERING MAY BE REQUIRED FOR ALTERNATE DESIGN LOADS.
- FIND ALLOWABLE COMPOSITE PANEL CLEAR SPAN IN TABLES FOR APPROPRIATE PANEL DEPTH, FACING THICKNESS, AND EPS CORE DENSITY SELECTED. **ZZZZZZ** INDICATES VALUES NOT VALID FOR USE.
- DEFLECTION NOTES:

- (RECOMMENDED, VERIFY WITH LOCAL JURISDICTION)
- USE L/120 FOR ALL MEMBERS SUPPORTING ROOFS OVER AN OPEN OR SCREEN-WALLED ROOM.
 - USE L/180 FOR ALL MEMBERS SUPPORTING ROOFS WITH A NON-PLASTERED CEILING OVER AN ENCLOSED ROOM.
 - USE L/240 FOR ALL MEMBERS SUPPORTING ROOFS WITH A PLASTERED CEILING OVER AN ENCLOSED ROOM.

MECHANICAL APPLICATION OF OSB AND SHINGLES TO EPS PANEL



OSB & SHINGLE ATTACHMENT DETAILS ILLUSTRATED HEREIN ARE INTENDED FOR USE WITH NON-HABITABLE SPACE ONLY.

MAXIMUM ALLOWABLE UPLIFT
-/+93.00 PSF

SHINGLE NOTES: (APPLICABLE TO THIS DETAIL ONLY)

SHINGLES MUST HAVE 0.65 OR GREATER SOLAR REFLECTANCE AS RATED BY SHINGLE MANUFACTURER. STARTER ROWS OF SHINGLES SHALL HAVE TWO LINES AT MID TAB AREA. SHINGLE ROW INSTALLED WITH TABS FACING IN THE UPWARD DIRECTION OF THE ROOF SLOPE. SUBSEQUENT ROWS OF SHINGLES INSTALLED WITH THE TABS FACING IN THE DOWNWARD DIRECTION OF THE ROOF SLOPE WITH ONE LINE OF ADHESIVE UNDER THE SHINGLE AT MID COVERED AREA.

NOTE:
FOR 550 PSF - ADHERE 5/8" OSB, STAGGERED, ON COMPOSITE PANEL AS SHOWN HEREIN. FASTEN OSB WITH #8 DRYWALL SCREWS WITH 10" MIN. FOR SPACING FOLLOWING THE CONTINUOUS ADHESIVE BEAD PATTERN.
FOR 593 PSF - ADHERE 5/8" OSB, STAGGERED, ON COMPOSITE PANEL AS SHOWN HEREIN. FASTEN OSB WITH #8 DRYWALL SCREWS WITH 5 1/4" MIN. FOR SPACING FOLLOWING THE CONTINUOUS ADHESIVE BEAD PATTERN.

DRAFT

2

STATE SEAL INDICATED BELOW
08/07/2014
VALID FOR (1) JOB(S) ONLY
VALID ONLY WITH ISSUED ENGINEER SEAL

FRANK L. BENNARDO, P.E.
160 SW 12th AVENUE, #106
DEERFIELD BEACH, FL 33442
PH: (954) 354-0660 Fax: (954) 354-0443
POWERED BY THE INNOVATIONS OF
ENGINEERING EXPRESS
EXPERIENCE MORE AT WWW.ENGEXP.COM

STRUCTALL BUILDING SYSTEMS
350 BURBANK ROAD
OLDSMAR, FL 34677
PH: (813) 855-2627
 DAL:2555
 GA:27525
 HI:1060688
 LA:30341
 ME:10178
 MD:28152
 MA:43224
 MN:43001
 NH:49491
 NJ:16927
 NY:2003019621
 RI:10664
 NC:4353500
 OH:666438
 PA:FE060991
 RI:7928
 SC:21507
 TX:96064
 VT:8182
 WA:042 038109
 DE:15009 CA 2282
 ID:11090 CA 2030

REMARKS	DRWN	CHKD	DATE
INIT ISSUE	RWN	TSB	08/05/14

SCALE: 14-1745
PAGE DESCRIPTION:
COPYRIGHT FRANK L. BENNARDO P.E.